CHITALDRUG DIVISION.

Notice dated 11th September 1929.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 21st October 1929, for constructing a Town Police Station at Hiriyur An approximate estimate quantities is given below. These quantities are not guaranteed. The work should be completed by the end of may 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 150 in cash or Currency Notes, as earnest money and be superscribed "Tender for constructing a Town Police Station at Hiriyur" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract showing the quantities for constructing the Town Police Station at Hiriyur.

No.	Details of work	Per	Quantity
1	Earthwork excavation gravelly soil for foundation and filling in basement with consolidation.	C.yd.	59
2	Stone in clay foundation and basement	C.ft.	2,157
3	Burnt brick in clay superstructure	,,	1,831
4	Burnt brick in chunam do	,,	441
5	Burnt brick in chunam coping with plastering ..	R.ft.	67
6	Burnt stone slabs 6" thick dressed and fixed ...	S.ft.	238
7	Teakwood lock-up doors with iron bars, etc., complete ...	,,	49
8	Honneywood battened door with iron clamps hinges, bolts, etc. complete.	,,	88
9	Honneywood windows battened with iron bars clamps, etc., complete.	,,	35
10	Honneywood ventilators with iron bars expanded, metal, etc., complete.	,,	11
11	Honneywood work wrought and put up with wood oiling ...	C.ft.	49
12	Roofing with Frst Class Mangalore tiles on teak reepers, etc., complete.	Sqr.	11·20
13	Ridge tiles set in mortar and cement pointing ...	R.ft.	40
14	Chunam borders over roof	,,	48
15	Teakwood ½" thick ceiling above rafters and below reepers to lock-up rooms including wood oiling.	S.ft.	210
16	Chunam plastering	Sqr.	43·03
17	White washing two coats	,,	43 03
18	Honneywood plain eave board	R.ft.	128
19	Tarringwood work two coats	Sqr.	3·00
20	Teakwood railing front of station as per plan ...	R.ft.	52
21	Flooring with First Class Mangalore tiles over 3" concrete bed and cement pointing.	Sqr.	3·92
22	Flooring with 1½" thick cuddapah slabs over 3" concrete bed and cement pointing.	,,	1·52
23	Teakwood gate with iron work, etc., complete	S.ft.	16
24	Silicate painting two coats	Sqr.	5·81
25	Constructing V shaped drain complete	R ft.	100
26	Flooring with grāvel including watering and tamping ...	S.yd.	12
27	Teakwood finials	Each	2
28	Teakwook pendants	,,	4
29	Cutting grooves and dressing stone pillars	,,	2
30	Constructing seats in latrine and fitting drain pipe, etc. ...	Lump sum	

Dated 11th September 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 21st October 1929, for Restoration of Jajur-Muradi Sanjeevaiyyankere in Chellakere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in Cash or Currency Notes, as earnest money, and be superscribed "Tender for Restoration of Jajur-Muradi Sanjeevaiyyankere in Chellakere Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract showing the quantities for Restoration of Jajur-Muradi Sanjeevaiyyanakere in Chllakere Taluk.

No.	Details of work	Per	Quantity
	I. Bund raising to R. L. 55·00.		
1	Earthwork including watering and tamping	C.yd.	5,790
2	Turfing	S.yd.	51·93
3	New stone revetment	C.yd.	476
4	Gravel backing	,,	263
5	Preparing and fixing grade stones	Each	21
6	Do Index stones	,,	21
7	Do Register number stone including cutting figures and painting.	,,	1
8	Do Guage stone do ...	,,	1
9	Do Bench markstones do ...	,,	2
	II. Breach filling.		
1	Clearing silt and sand	C.yd.	190
2	Benching soft rock	Lump	sum
3	Cutting grips to old bund	Lump	sum
4	Burnt brick in surki mortar	C.ft.	640
5	Earthwork filling in breach including watering and tamping, mixing gravel and earth in proportion of 1 to 3.	C.yd.	680
6	New stone revetment	,,	81
7	Gravel backing	,,	37
8	Turfing	S yd.	165
	III. Constructing a new sluice.		
1	Cut opening the bund including revetment in slope of ½ to 1 and refilling earth with perfect consolidation.	C.yd.	98
2	Concrete in surki mortar	C.ft.	94
3	Burnt brick in do	,,	226
4	Burnt stone slabs 6" thick including drilling hole and fixing ...	S.ft.	29
5	Orifice slab do do do ...	Each	2
6	Surki mortar plastering	Sqr.	3·00
7	Providing and fixing 6" cast iron pipe including lead joint ..	R.ft.	36
8	Wooden plug with $2\frac{1}{2}" \times \frac{1}{4}"$ iron bar with locking arrangements	Lump	sum
	IV. Constructing a weir of 130' long.		
1	Approach and draft clearing using earth to bund	C.yd.	334
2	Dry stone work	C.ft.	390
3	Stone in surki mortar	,,	135
4	Surki mortar plastering	Sqr.	2·75
5	Burnt stone slab 6" thick dressed and fixed	S.ft.	15
6	Forming bank, building wings and other unforeseen works ...	Lump	sum